

Quality Control Guidelines in Small Scale Concrete Masonry Facilities Using Nondestructive Testing and Statistical Process Control

Sikandar Sajid ^[1]

Luc Chouinard ^[2]

[1] PhD Student, Civil Engineering and Applied Mechanics, McGill University, Canada

[2] Professor, Civil Engineering and Applied Mechanics, McGill University, Canada



Contents

- Introduction
- Experimental Program
- Resonant Frequency Test
- Quality Control Procedures
- Uncertainties in Destructive test (DT) and Non-destructive Test (NDT)
- Statistical Process Control
- Results
- Conclusions



Introduction

- ▣ Masonry is a prime building material in construction industry
- ▣ Baked clay and concrete masonry units (CMU)
- ▣ CMU is rapidly replacing the baked clay bricks
- ▣ CMU manufacturing operations
 - Large scale automated production plants
 - Small scale production facilities



Introduction

- ▣ The small scale CMU production facilities are primarily artisanal
- ▣ Lack effective procedures for:
 - Quality assurance testing and control guidelines
- ▣ The use of substandard CMU was the one of the primary causes of widespread destruction in:
 - Kashmir 2005, Pakistan Earthquake
 - Haiti 2010 earthquake



Introduction

- ▣ Quality assurance and control
 - Destructive testing (DT) using Universal testing machine
 - Nondestructive Testing (NDT) using surface hardness and stress wave techniques
- ▣ Destructive testing is reliable, however,
 - Expensive and extent of testing is limited



Introduction

- ▣ Need for an alternative to conventional destructive test using UTM
 - Cost effective
 - Practicable and acceptable reliability of test results
- ▣ NDT is an efficient and cost effective technique, however
 - Indirect testing
 - Reliability of the test results may not be as high as DT

Introduction






Introduction


- ▣ This work attempts to:
 - Explore various available NDT methods for strength estimation of CMU
 - Reliability of test results
 - Quality assurance and control using NDT
 - Reliability of the proposed method

Experimental Program



Experimental Program

- ▣ Number of tests
- ▣ Parameters investigated
- ▣ Repeatability of measurements
- ▣ Results and sources of variability






Resonant Frequency Test Results

- The focus of this work is the resonant frequency test (RFT) as NDT
- Resonant frequency test conducted as per ASTM C215
- The results of the concrete vibration under the stress wave are recorded in the longitudinal mode
- The correlation using regression for the RFT with DT

Resonant Frequency Test Results



Regression Analysis		Goodness of fit:	
$\ln(fc) = a_1 * RFT + a_2$		SSE	0.9362
Coefficients (with 95% confidence bounds):		R ²	0.9444
a₁ =	0.0006869 (0.00065, 0.00072)	Adjusted R ²	0.9438
a₂ =	4.04 (3.835, 4.244)	RMSE	0.1031




Quality Control Procedures

- ▣ Limit state design (CSA S304, Design of Masonry Structures)
accounts for uncertainties in
 - Strength of the materials
 - Loads on the structure
- ▣ Nominal Compressive strength
 - 5% exclusion limit with 75% confidence level

(CSA S408-11 Guidelines for the development of limit states design standards)

Quality Control Procedures




Definition of the 5% exclusion limit

- 5% exclusion limit
- Assumption: Normal distribution on f'_c (CSA 165.1-14)
 - ($n = 5+$ if $\text{CoV} < 15\%$, and $n = 10+ > 15\%$)

$$f_{cn} = \bar{X} - 1.645s$$

Quality Control Procedures

- 5% exclusion limit with 75% confidence level
- Defined as $f_{cn} = \bar{X} - k_1 s$, where k_1 is a function of the confidence level and sample size.



Uncertainties in DT and RFT

- ▣ The uncertainties are quantified using variance
- ▣ Considering a target nominal strength value of 20 MPa,
- ▣ The uncertainties in DT is 2.4 MPa by assuming a coefficient of variation of 10% (mean is 24 MPa)

- ▣ The uncertainty in NDT test results is (for lognormal):

$$\sigma_{\varepsilon}^2 = e^{2\theta + \omega^2} (e^{\omega^2} - 1)$$

$$\sigma_{\varepsilon}^2 = (2.4 \text{ MPa})^2$$

- ▣ Where $\theta = 8.15$ and $\omega^2 = 0.10$ from the regression

Uncertainties in DT and RFT

- ▣ NDT is indirect testing
- ▣ The uncertainties in strength estimation using RFT is:

$$\sigma_{Total}^2 = \sigma_{indirect\ observations}^2 + \sigma_{fc}^2$$

- ▣ The additional uncertainties due to NDT can be reduced by increasing the number of observations above those required for DT.



Statistical Process Control

- ▣ Statistical hypothesis test
 - Type I error (α): Reject process that meets specs (e.g. 20 MPa)
 - Type II error (β): Accept process that does not meet specs (< 20 MPa)
- ▣ $\alpha = 25\%$ (i.e. 75% confidence level of CSA S408-11)
- ▣ Power of the test ($1 - \beta$):
 - Probability of detecting process that deviates from specs (by δ)
 - Operating Characteristic curve (β as a function of δ and n)




Statistical Process Control

- ▣ Reliability of quality control using operating characteristic curves
- ▣ Function of:
 - Sample size n
 - Coefficient of variation (5%, **10%**, 15%)
 - Significance level (25%)

Results

□ Quantification of Uncertainty

▣ Coefficient of Variation = 5% ($n > 5+$)




Results


Quantification of Uncertainty

■ Coefficient of Variation = 10% ($n > 5+$)

f_{cn} minimum = 18 MPa with 85% POD



$n = 5$ for DT




$n = 10$ for NDT

Results

Quantification of Uncertainty

f_{cn} minimum = 18 MPa with 85% POD

■ Coefficient of Variation = 15% ($n > 10+$)



Conclusions

- NDT can be employed in quality control in small scale facilities given a calibration equation is already developed
- The number of samples needed for NDT to achieve the same power as the DT is determined objectively to satisfy the standards
- The effect of the coefficient of variation affects the required number of samples
- A high coefficient of variation may be expected for small artisanal CMU facilities

Future work

- ▣ Determine tolerable deviations from specifications and probability of detection using reliability and risk analysis for shear walls
- ▣ Review of existing standards
 - Wide range of quality control procedures
 - Some inconsistencies in procedures



Thanks